United States Coast Guard



ACSA INSPECTION BOOK

| Name of Vessel | |
|-----------------------------|-------------------------|
| Official Number | Class/Loadline |
| Date Completed | Location |
| Vessel Type | |
| ☐ Long Liner | ☐ Trawler |
| Inspection Type | |
| ☐ Exemption renewal | ☐ Mid-period |
| ☐ Dry-dock inspection | □ COC |
| ☐ Internal Structural (ISE) | ☐ Other |
| Inspectors | |
| | |
| 1 | 2 |
| A -Admin | G -Machinery |
| B -Stability | H-Life saving |
| C -Dry-dock | I-Fixed fire fighting |
| D-Shaft & Rudder | J -Fire & Safety |
| E-Hull Gauging | K -Drills |
| F -Watertight integ. | L-Comms & Nav. |
| | ACSA 840 Rev. 11/09 |

| A - Administration | Interval | References |
|--|------------|-------------------|
| ☐ 1. Completion of Annual Certificate of Compliance (COC) Exam | Annually | ACSA Agreement |
| a. If conducted by a 3rd party organization | | Compliance Matrix |
| \square (1) Confirm a valid COC was issued in the last year. | | Annex 2 |
| b. If conducted by the Coast Guard | | |
| \Box (1) Exemption letter will be endorsed as satisfying the | | |
| requirement for having a COC certifying that the | | |
| requirements of 46 CFR Part 28 have been met. (2) If a reinspection, the Coast Guard Exemption Letter | | |
| will be endorsed to confirm that an annual COC | | |
| exam was completed. | | |
| B - Vessel Stability | Interval | References |
| ☐ 1. Stability Instructions | Annually | Kererences |
| | Ailliually | 46 CFR 28.530 |
| a. Not greater than 5 years since last inclining or | | 40 CFK 28.330 |
| verification of stability by deadweight survey. | | 0::14004 |
| O b. Examine loading marks located on side of vessel to | | Original ACSA |
| ensure they match the locations as described in the | | Agreement B 1 |
| stability instructions. | | |
| C. Examine instructional addendum to stability instruction | | |
| to ensure it describes each of the following: | | |
| (1) Lists each: | Annually | Original ACSA |
| (a) Watertight bulkhead. | | Agreement B 2(b) |
| (b) Watertight closure to include size and type. | | |
| (c) Weather-tight closure to include the type, size, | | |
| coaming, vent heights and location | | ABS |
| (d) identify automatic closure devices and operating | | LL-11D |
| stations for each of the following located on the main | | |
| deck or above. | | |
| Doors, Hatches, | | |
| • Scuttles, • Chutes, | | |
| Tank vents, ● Ventilation devices. | | |
| (2) Listing of all sea valves | Annually | Original ACSA |
| (a) Includes location, size, type and remote operators | | Agreement B 2(c) |
| Hull freeboard, | | |
| Underwater body. | | |
| (3) Factory Sump Pumps | Annually | |
| (a) Examine calculations to ensure sufficient capacity | Aimuany | |
| on each side of the vessel of twice the inflow into the | | Original ACSA |
| | | • |
| factory as determined by a naval architect. | | Agreement B 2(d) |
| (b) If no sump pumps are used because freeing ports | | |
| and /or scuppers are used, this must be listed in the | | |
| stability addendum. | | |
| Addendum must list size and number of | | |
| freeing ports and drain lines. | | |

| C - Drydock and Internal Structural Exam | Interval | References |
|---|---|---------------|
| 1. Propeller(s) | 2/5yrs > 3yrs | 46 CFR |
| 2. Stern bushing(s) | 2/5yr $4 > 3$ yrs | 61.20-5(a) |
| ☐ 3. Sea connections | 2/5yrs >3 yrs | 11 11 |
| 4. Weldments | 2/5yrs >3 yrs | NVIC 7-68 |
| Oa. Visually examine condition of all welds for | | Section V |
| (1)Washed out welds, (2)Cracking, (3)Excess pitting/corrosion | | |
| 5. Shell plating | 2 / 5yrs > 3yrs | |
| Oa. Visually exam condition of all shell plating | | |
| 6. Sea chests | 5 yrs | 46 CFR |
| O a. Open for inspection | J 3 315 | 61.20-5 |
| Ob. Check all welds, plating and thru hull penetrations | | 01.20 3 |
| 7. Sea valves | 5 yrs | 11 11 |
| | 3 yıs | |
| Oa. All valves within 6 inches and below of the deepest load waterline | | |
| must be opened for inspection and examined. | | |
| (1) Seats (2) Guides | | |
| (3) Body (4) Stem | | 4 D.G. 1 |
| Ob. Valves must be located as close as possible to the side shell plating | | ABS rules |
| Oc. Valves are to be steel, bronze or other approved material. | | 4-4-2/19 |
| \Box (1) Valves of ordinary cast iron are not acceptable | | |
| Od. Valves employing resilient material to seal must be a "Category A" | | |
| Oe. If butterfly valves are used, they must be of the lug type. | | |
| \square (1) Wafer-type valves are not acceptable | | |
| 8. Sea Strainers | 5 yrs | 46 CFR |
| Oa. Open for inspection and clean | | 61.20-5(b) |
| 9. Valve for emergency bilge suction (if equipped). | 5 yrs | " " |
| Oa. Open for inspection and examine | | |
| □ 10. Internal Examination of Integral Fuel Oil Tanks | 2/5yrs >3 yrs | 46 CFR |
| (see 46CFR91.43-1 number of tanks that must be opened for inspection) | · | 91.43-1 |
| Oa. Examine all for wastage / damage of: | | |
| \square (1) All side shell, bulkhead and tank top plating | | |
| \square (2) Frames | | |
| \square (3) Welds | | |
| ☐ 11. Internal examination internal spaces/voids/cofferdams/ballast tanks | 5 yrs | 46CFR |
| (see 46CFR91.41-1 number of tanks that must be opened for inspection) | | 91.40-3 |
| Oa All side shell, bulkhead and tank top plating | | |
| Ob Frames | | |
| Oc Welds | | |
| ☐ 12. Hull Markings | 2 / 5yrs > 3yrs | 46CFR |
| Oa. Fore and aft draft marks | - / - / - / - / - / - / - / - / - / - / | 97.40-10 |
| Ob. Maximum loading mark location in terms of mid-length location by | | |
| frame number and distance in inches from the molded main deck line | | |
| to the bottom mark as identified in the addendum to the stability ltr | | |
| \Box (1) Mark 12 inches long | | Original ACSA |
| \square (1) Wark 12 liches long \square (2) 1 inch wide | | Agreement |
| ``´ | | Agreement |
| \square (3) Horizontal white line centered on listed location | | |
| ☐ (4) Located port and starboard sides | | |
| \square (5) Permanently marked by weld bead or punch marks | | |

| C - Drydock and Internal Structural Exam | Interval | References |
|---|-----------------|------------------|
| 13. Hull Repairs | When | MSM Vol II |
| Oa. When repairs are required to the underwater body, framing | required | Ch B3.B2 |
| or other structural members, the cognizant OCMI must be notified | | |
| \square (1) Guidance for repairs should be in accordance with | | NVIC 7-68 |
| Navigation and Vessel Inspection Circular (NVIC 7-68) & | | |
| \square (2) Good marine practice. | | |
| ☐ 14. Ground Tackle | 5 yrs | ABS rules |
| Oa. Ensure suitable for vessel. | | 3-5-1 |
| Ob. Anchors and chain / wire rope are to be ranged. | | |
| (1) Chain to be gauged; Maximum wastage allowed is 12% | | ABS: 7-3-2-5.1.4 |
| ☐ 15. Vital System Piping (essential to the safety of the vessel | Annual | <u>46 CFR</u> |
| its passengers and crew). | | 56.07-5(f) |
| Oa. Must meet minimums in 46 CFR Subchapter F. | | 56.50-1 |
| ☐(1) Fuel oil for main propulsion / emergency generators | | |
| ☐(2) Lubricating oil systems | | 56.50-60 |
| \square (3) Cooling water for main propulsion / emergency generators | | |
| ☐(4) Bilge and ballast systems | | 56.50-80 |
| ☐ (5) Steam systems | | |
| \square (6) Starting and control air systems | | 56.50-95 |
| \square (7) Fire main and firefighting systems | | |
| Ob. Materials must be as specified in subpart 46CFR56.60 | | 56.50-57 |
| Oc. Welding must be with approved weld procedures | | 56.50-15 |
| using certified welders. | | 56.6 |
| Od. Exemption: existing systems can remain unless | | 56.7 |
| \square (1) The piping is declared manifestly unsafe | | |
| ☐(2) Piping is being repaired or replaced | | |
| ☐ 16. Non-metal expansion joints | | <u>46 CFR</u> |
| Oa. External Inspection. | Annual | 61.15-12 |
| \square (1) Inspect for excessive wear, fatigue, deterioration, damage, | | |
| misalignment, improper flange to flange spacing, and leakage | | |
| Ob. Internal examination | When required | |
| \square (1) Must be conducted when external examination reveals | Min. 10 yrs | |
| excessive wear or other signs of deterioration or damage. | | |
| ☐ 17. Pressure Vessels (Compressed air receivers - greater than 5 cf) | | <u>46CFR</u> |
| Oa. Internal and external examination. | 5 yrs | 61.10-5 |
| Ob. Hydrostatic testing unless examined internally by a | 5 yrs | |
| marine inspector & no defects found which would impair the | | |
| safety of the pressure vessel. | | |
| Oc. Pressure Relief Valves | | |
| ☐ Pressure test: Set to relieve at or below 10% above MAWP | 2 / 5yrs ≯ 3yrs | |
| ☐ Upper range on gages not less than 1.2X or more than 2X | | 54.15-5 |
| the relief valve setting | | |

| D Tail Shaft and Rudder Examinations | Interval | References |
|---|----------------------|-------------------|
| ☐ 1. Each tailshaft must be drawn and visually inspected as follows | | <u>46 CFR</u> |
| O a. Multiple shafts | 5 yrs | 61.20-18 |
| O b. Tailshafts: | 5 yrs | 61.20-17(c) |
| \square (1) with inaccessible portions fabricated of materials | | 61.20-17(d) |
| resistant to corrosion by sea water, or | | |
| \square (2) fitted with a continuous liner, or | | |
| (3) a sealing gland which prevents sea water from | | |
| contacting the shaft. | | |
| O c. Tailshafts with oil lubricated bearings | Not to be | |
| \square (1) As long as each of the following is done: | pulled | 61.20-17(e) |
| (a) tailshaft readings | Every DDX | |
| (b) inboard seal assemblies examined | Every DDX | |
| (c) analysis of tailshaft oil lubricant in accordance with | Min. | |
| manufacturer's recommendations to determine: | 6 months | |
| · max bearing material content, | | |
| · presence of other contaminants | | |
| (d) NDT tapered tailshaft and keyway in place (if fitted) | 5 yrs | 61.20-17(e)(4)(i) |
| (e) NDT coupling bolts and flange for props | When | |
| with coupling in place (if fitted) | removed | |
| O d. Tailshafts – All others | 2/5 yrs≯3yrs | 61.20-17(b) |
| ☐ 2. Examination requirements for all shafts as applicable | 2/5 yrs 3yrs | <u>46 CFR</u> |
| O a. Tailshaft with fitted key | · | 61.20-18(b) |
| (1) NDT of forward 1/3 of the shaft's taper section | | |
| (2) Visual inspection of entire shaft | | |
| O b. Tailshaft with a propeller fitted by means of coupling flange | | 61.20-18(c) |
| (1) NDT coupling flange, fillet at propeller end, coupling bolts | | |
| (2) Visual inspection of entire shaft | | |
| ☐ 3. Rudder and Rudder Shaft Examination | 2/5 yrs 3 yrs | ABS Rules |
| O a. Ensure rudder bearing clearances are within manufacturer's | · | Part 3-2-11 |
| specifications. | | |
| O b. Examine: | | |
| (1) Rudder plating, weldments, water leakage. | When | |
| (2) Rudder stocks, and if fitted with a tapered stock, the | removed | |
| keyways, keys and locking nut. | | |
| (3) Pintles. | | |
| (4) Gudgeons. | | |
| (5) Coupling bolts, if fitted with flange couplings. | | |
| (6) Rudder supporting structure, skegs, fairwaters/fairings, | | |
| shoe, pieces, carrier, and anti-lifting devices, if fitted. | | |

| D Tail Shaft a | nd Rudder Examina | ations | Interval | References |
|---|--------------------------|--------------------------------------|---------------|----------------|
| ☐ 4. Examination requirements for tailshaft bearings. | | | <u>46 CFR</u> | |
| Water lub | oricated bearings (exce | pt rubber) must be refurbished | | 61.20-23(a) |
| as follow | s: | | | |
| | Propelling machinery l | located amidships | | |
| For shaft | diameters | After stern tube bearing refurbished | | 61.20-23(a)(1) |
| Greater than | Less than or equal to | When clearance worn down to | 1 | |
| | 229 mm (9 in) | 6.4 mm (0.25 in) | 1 | |
| 229 mm (9 in) | 305 mm (12 in) | 7.95 mm (0.3125 in) |] | |
| 305 mm (12 in) | | 9.53 mm (0.375 in) |] | |
| $\square (2)$ | Propelling machinery l | located aft | | |
| For shaft | diameters | After stern tube bearing refinbished | | 61.20-23(a)(2) |
| Greater than | Less than or equal to | When clearance worn down to | 1 | |
| | 229 mm (9 in) | 4.8 mm (.1875 in) | 1 | |
| 229 mm (9 in) | 305 mm (12 in) | 6.35 mm (0.25 in) | | |
| 305 mm (12 in) | | 7.93 mm (0.3125 in) | 1 | |
| | | rings must be refurbished when | 2/5 yrs>3yrs | 61.20-23(b) |
| · | ater groove is ½ the ori | ginal depth. | | |
| E - Hull Audio (| | | Interval | References |
| | gauging requirement | | 5 yrs | |
| ☐ 2. Gaugings | shall include, but no | t limited to the following: | | Original |
| ○a.Three tra | insverse sections in the | ne midship 0.5L. | 5 yrs | ACSA Agreement |
| ○b. Internals | s of the fore and after | saltwater peak tanks. | | Section E |
| ○c. Wind an | nd water strakes, port | and stbd, full length. | | |
| ○d. All expo | osed main deck platir | ng & superstructure deck. | | ABS Rules |
| ∩e. Two sho | ots on each bottom pl | ate at the discretion of the | | Part 3-2 |
| ı | g Marine Inspector. | | | |
| ○f. Sea ches | • | | | |
| ı | ispected areas throug | hout the hull | | |
| | | own, the owner in consultation | | |
| | • | an accredited marine surveyor | | |
| | • | • | | NVIIC 7 (0 |
| _ | calculation of the rec | • | | NVIC 7-68 |
| _ | | % of calculated plate thickness. | | |
| | | num standards for scantling | | |
| | nsions. | | | |
| □ 4. Obtain co | py of gauging report. | | 5 yrs | |

| F - Water tight integrity (plan submitted by owner) | Interval | References |
|---|----------|-----------------|
| ☐ 1. All watertight/weathertight closures | Annually | Original ACSA |
| as listed in the stability addendum or ABS LL 11d: | | Agreement |
| a. Clearly labeled/identified on-board vessel & correlate to list | | Section F 1 |
| ○ b. Labeled "Opening authorized for transit only – keep closed at sea". | | |
| ○ c. All dogs operable | | ABS LL-11D |
| O d. Chalk or light tested for fit and watertight integrity | | |
| O e. Seal not painted, badly cracked or deteriorated | | |
| O f. Examine sealing edge of closure frame | | |
| ☐ 2. All watertight/weathertight closures as listed in stability booklet | Annually | Original ACSA |
| addendum shall have administrative controls for managing the status | | Section F 2 |
| as listed below: | | |
| a. Detailed preventive maintenance schedule for each of the | | |
| closures listed. | | |
| ○ b. Written instructions for at-sea security watches. | | |
| (1) Each closure listed must include required closure status for | | |
| at least the following vessel conditions: | | |
| (a) When the vessel is in transit | | |
| (b) When the vessel is actively fishing/processing | | |
| (c) When idle on the fishing grounds | | |
| ☐ 3. Six-dog "quick acting" watertight closures on the aft 1/3 of the | Annually | ACSA Guide |
| main deck and other locations that pose a particular risk to | | Section F |
| down flooding. | | Discussion |
| a. Door coamings minimum of 24 inches in height | | |
| ☐ 4. If a particular hazard regarding the status of watertight or weather | Annually | Original ACSA |
| tight closures is identified during a vessel survey, an appropriate | | Agreement |
| engineering solution shall be developed by the owner, naval | | Section F 4 |
| architect, to the satisfaction of the OCMI. | | |
| ☐ 5. Factory space high water alarms | Annually | Section F 5 |
| a. Installed in each corner of the factory | | |
| O b. Alarm at water level greater than 6 inches | | |
| C. Time delay (up to 5 seconds) may be allowed. | | |
| O d. Visual alarm | | |
| (1) Installed in the factory. | | |
| (2) Installed at the machinery control flat. | | |
| (3) Installed in the pilot house at normal piloting station | | |
| instrument panel | | |
| (a) Distinctive indicator | | |
| O e. Audible alarm in pilot house | | |
| ☐ 6. Vent Heights | Annually | 46 CFR 42.15-50 |
| a. Ensure vent heights are min 30 inches above the main deck. | | |
| (1) Examine condition of closures. | | |
| (2) Examine vent balls and seats. | | |

| G - Machinery Inspection | Interval | References |
|---|----------|------------------|
| ☐ 1. Fuel System | Annually | <u>46 CFR</u> |
| a. Fuel supply piping on the pressure side must be: | | |
| (1) Vessels > 100 GT | | |
| (a) Seamless piping of steel, annealed copper or brass | | 56.50-75(a) |
| or tubing or nickel copper meeting the requirements | | |
| 56.60 for materials and 56.50-70(a)(2) for thickness. | | |
| (2) Vessels $\leq 100 \text{GT}$ | | 56.50-75(b) |
| (a) Copper, nickel copper or copper nickel | | |
| Minimum wall thickness .035 inches | | |
| · Seamless steel pipe or tubing of equivalent | | |
| level of safety may be used. | | |
| O b. Non-metallic flexible hose under high pressure of at least 10 psi | | 56.50-75(b)(3) |
| allowed only where flexibility is required to prevent damage from | | 56.50-75(b)(2) |
| vibration. Such hose must not be more than 30 inches in length. | | |
| (1) Fuel / hydraulic hoses must meet J-1942 or SAE J-1942-1. | | 56.60-25(b) |
| (2) Hose Hose fittings | | , , |
| (a) Fittings must comply with SAE J-1475 | | 56.60-25(b)(5) |
| (b) Push-lock fittings are not acceptable | | |
| (3) Exceptions to the 30 inch rule will be allowed on a case by | | |
| case basis. | | |
| (4) In addition to the requirements above approved fire sleeve | | |
| material as listed in the SAE qualified hose list must be | | |
| over the approved hose. | | |
| O c. Sight gauges on tanks | | 58.50-10(a)(6) |
| (1) Must be welded or brazed to the tank | | |
| (2) Sight gauge must be heat resistant material | | |
| (3) Protected from mechanical damage | | |
| (4) Both ends of sight gauge must be fitted with devices that will | | |
| automatically close should the gauge break. | | |
| ☐ 2. Exhaust piping within 15 feet of fuel, lube oil, or hydraulic oil sources. | Annually | 28.380(b) |
| O a. Must be insulated or guarded to prevent ignition. | | |
| ☐ 3. Diesel propulsion machinery tests | Annually | 58.05-10 |
| a. Obtain copy of the written test procedures | | |
| O b. Automatic shut-down on overspeed (if installed)*. | | Table 62.35-50 |
| C. Low lube oil pressure alarm. | | 58.05-10 |
| Od. Jacket water high temperature alarm | | ABS Rules: 4-7-1 |
| \square 4. Diesel prime mover tests for generators and auxiliary equipment | Annually | <u>46CFR</u> |
| a. Obtain copy of written test procedures | | 111.12-1(c) |
| O b. Automatic shut-down on overspeed* | | 112.50(g) & (h) |
| © c. Alarm and shut-down of low lube oil sensor | | |
| O d. Jacket water high temperature alarm | | 112.50(h) |
| * If diesels with computer automation, provide | | |
| calibration standards set by the manufacturer. | | |

| G - Machinery Inspection | Interval | References |
|--|----------|----------------|
| ☐ 5. Examination of tests and records | Annually | ACSA Agreement |
| a. At the request of the examiner the owner/operator will | | section G 4 |
| provide preventive maintenance records. | | |
| (1) Examine records | | |
| (2) Conduct tests and inspections as necessary to ensure | | |
| safe operation of: | | |
| (a) Main propulsion | | |
| (b) Electrical generation machinery | | |
| (c) Auxiliary or associated equipment | | |
| ☐ 6. Fire safety hazard survey | Annually | ACSA Agreement |
| a. Conduct survey of machinery spaces to identify any other | | section G 5 |
| fire safety hazards not covered in ACSA agreement. | | |
| ☐ 7. Fuel tank vents | Annually | 46CFR |
| O a. Inspect flame screen (minimum 30 X 30 mesh) | | 56.50-85(a)(7) |
| O b. Operation and seating of ball check valves | | |
| ☐ 8. Electrical wiring on main engines | Annually | |
| a. Electrical cables connecting starting batteries to main | | 46CFR |
| propulsion and starters | | 111.60-1(a) |
| O b. Cables connecting main propulsion engines to generators | | |
| (1) Must meet IEEE Std 45, IEC 92-3, MIL-C-24640A, | | |
| or MIL-C-24643A | | |
| (2) The use of electrical welding cables is not authorized | | |
| H - Life Saving Equipment | Interval | References |
| 1. Life raft launching | Annually | ACSA Guide |
| a. Mounted so can be manually launched by one person | | section H 1 |
| ☐ 2. Embarkation ladders must be installed for each liferaft embarkation | Annually | section H 2 |
| station that is five feet or more above the waterline | | |
| in normal operating conditions. | | |
| ☐ 3. Personal Marker Lights (PML) | Annually | section H 3 |
| O a. Each immersion suit is required to be fitted with a Coast Guard | | |
| approved strobe type PML. | | |

| I - Fixed Fire Fighting Equipment & Arragnements (46CFR76-15 applies) | | | |
|--|----------|------------------|--|
| ☐ 1. Spaces requiring a fixed fire fighting system | Interval | References | |
| O a. Any space containing: | Annually | <u>46 CFR</u> | |
| (1) Internal combustion engine greater than 50 hp. | | 28.320(a) | |
| (2) An oil-fired boiler | | " " | |
| (3) An incinerator | | " " | |
| (4) Gasoline storage tank(s) or other flammable materials | | " " | |
| (5) Paint lockers over 60 cubic feet in volume | | ACSA Guide Sec.I | |
| \square 2. Vessel specific fixed fire fighting systems certified by a professional | Annually | 46 CFR 76.15 | |
| engineer for compliance with 46 CFR 76.15 and NVIC 6-72 change 1 | | NVIC 6-72, Ch 1 | |
| ☐ 3. Spaces protected by fixed CO2 systems not more than 300 lbs | Annually | <u>46 CFR</u> | |
| O a. CO2 cylinders may be located inside the space protected | | 76.15-20(b) | |
| (1) If cylinders are located inside the space protected | | 76.15-10(a) | |
| (a) Heat actuator is required that will automatically | | 76.15-20(b) | |
| operate in addition to the remote pulls. | | | |
| (2) If cylinders are stored in a CO2 room | | 76.15-20(a) | |
| (a) Room must be well ventilated | | 76.15-20(b) | |
| (b) Must not be located in an area where the ambient | | | |
| temp exceeds 130 deg F | | | |
| (3) Cylinders must be securely fastened and supported | | 76.15-20(d) | |
| O b. Controls must be located outside the space protected | | 76.15-10(a) | |
| (1) Not located in an area that could be cut off or made | | | |
| inaccessible in the event of fire in the space in the event of | | 76.15-10(h) | |
| fire in the space protected. | | | |
| (2) Complete but simple instructions for operation of the | | | |
| system must be located in a conspicuous place near pull | | | |
| boxes and at the control station located at the cylinder | | | |
| location. | | | |
| O c. Alarm and time delay is required unless space is small and | | 76.15-10(f) | |
| there is suitable horizontal escape from the space. | | | |
| (1) Perform functional test | | | |
| (2) Cylinders weighed | | | |
| (3) System must alarm for at least 20 seconds before | | | |
| CO2 is released into the space. | | | |
| O d. Ventilation | | | |
| (1) Protected spaces with mechanical ventilation must | | 76.15-35(a) | |
| automatically shutdown on activation of the CO2 system. | | | |
| (2) Means for closing all openings to the space protected | | 76.15-35(c) | |
| must be provided and must be able to be accomplished | | | |
| from outside the space. | | | |


| I - Fixed Fire Fighting Equipment & Arragnements (46CFR76-15 applies) | | |
|--|----------|---------------|
| ☐ 4. Spaces protected by fixed CO2 systems more than 300 pounds | Interval | Reference |
| O a. CO2 cylinders <u>must</u> be stored outside the space protected. | Annually | <u>46 CFR</u> |
| O b. Controls <u>must</u> be located outside the space protected | | 76.15-20(a) |
| (1) Not located in an area that could be cut off or made | | 76.15-10(a) |
| inaccessible in the event of fire in the space protected. | | |
| (2) Complete but simple instructions for the operation of the | | |
| system must be located in a conspicuous place near pull | | |
| boxes and at the control station located at the cylinder location. | | |
| O c. Alarm and time delay is required | | |
| (1) Perform functional test | | |
| (2) Cylinders weighed | | 76.15-10(f) |
| (3) System must alarm for at least 20 seconds before CO2 is | | |
| released into the space. | | |
| O d. Ventilation | | |
| (1) Protected spaces with mechanical ventilation must | | 76.15-35(a) |
| automatically shutdown on activation of the CO2 system. | | |
| (2) Means for closing all openings to the space protected must | | 76.15-35(c) |
| be provided and must be able to be accomplished from | | |
| outside the space. | | |
| ☐ 5. Pre-engineered fire extinguishing systems | Annually | 46 CFR |
| O a. May be used in place of fixed CO2 systems provided they are | | 28.320(d) |
| qualified by the restrictions and standards set forth in 46 CFR 28.320 | | |
| (1) Only in spaces less than 33.98 cubic meters (1200 cubic ft.) | | |
| that are normally unoccupied. | | |
| (a) Small main engine spaces | | |
| (b) Paint / flammable storage lockers | | |
| O b. Must be approved by Commandant for the intended application. | | Original ACSA |
| O c. Capable of manual activation from outside the space in addition | | Agreement |
| to any automatic actuation devices | | section I 3 |
| O d. Automatically shut down all power ventilation to the space | | |
| protected. | | |
| O e. A visible and audible alarm must sound at the vessel's operating | | |
| station, indicating discharge. | | |
| ☐ 6. Heat detectors in spaces containing fixed gas fire extinguishing systems. | Annually | Original ACSA |
| O a. Heat detector alarms (rate of rise / maximum temperature) must be | | Agreement |
| installed in each space fitted with a fixed gas fire extinguishing system | | section I 4 |
| (1) CG approved systems will comply with 46CFR161.002 or | | |
| (1) Co approved systems will compry with 1001 kt of 1002 of | | |
| (2) non-CG approved systems meeting criteria listed in | | |


| I - Fixed Fire Fighting Equipment & Arragnements (46CFR76-15 applies) | | | |
|---|----------|-----------------|--|
| ☐ 7. CO2 detection system | Annually | NFPA 12 | |
| O a. CO2 detection system installed in any accommodation space | • | Chap 4.3.3.1.1 | |
| where CO2 cylinders are stored. | | 1 | |
| (1) Test the function of the CO2 detection system | | | |
| ☐ 8. Smoke detectors in all accomodation spaces | Annually | ACSA Guide | |
| a. Acceptable detectors include: | | section I | |
| (1) Independent modular smoke detector. | | discussion | |
| (a) Must meet UL-217 as "Single Station Smoke | | | |
| Detector – Also suitable for use in Recreational | | | |
| Vehicles." | | | |
| (b) Other fire / smoke/ heat detectors may be approved | | | |
| for use by the local OCMI. | | | |
| (2) Smoke actuated fire detecting unit | | | |
| (a) Must be installed IAW 46CFR76.33. | | | |
| ☐ 9. Structural fire protection | Annually | ACSA Guide | |
| a. A-0 boundaries must isolate all interal combustion | | section I | |
| machinery spaces. | | discussion | |
| ☐ 10. Non-combustable insulation. | Annually | section I | |
| a. Any insulation replaced in hidden spaces should be of a | | | |
| non-combustible material IAW 46CFR Subchapter Q. Any | | | |
| exceptions are at the discretion of the local OCMI. | | | |
| J - Other Fire Fighting and Safety Equipment | Interval | References | |
| ☐ 1. Portable fire/dewatering pump | Annually | <u>Original</u> | |
| a. Must be independently powered | | <u>ACSA</u> | |
| O b. Must be stowed outside the engine room | | | |
| © c. Sufficient suction hose to reach water from highest lift. | | section J 1 | |
| Od. Sufficient 1.5 inch fire hose to reach any part of the vessel | | section J 2 | |
| (1) Hose(s) fitted with nozzle of corrosion resistant material. | | | |
| (a) Nozzle must be dual purpose capable of providing | | section J 3 | |
| solid or straight stream, and spray pattern. | | | |
| O e. Pump capable of producing two effective 40 foot streams | | | |
| from standard 1.5 inch fire hose. | | | |

| J - Other Fire Fighting and Safety Equipment | Interval | References |
|---|----------|--------------|
| ☐ 2. Fireman's Outfits. | Annually | |
| O a. Vessels with fewer than 26 people on board shall have 2 outfits. | | sections |
| O b. Vessels with 26 or more people on board shall have 4 outfits. | | J 4 & 5 |
| O c. Fireman's outfit shall include | | |
| (1) One positive pressure self-contained breathing apparatus, SCBA | | 46 CFR 96.35 |
| (a) With attached lifeline | | |
| (2) Protective clothing with retro-reflective tape | | |
| (3) Rigid helmet | | |
| (4) Gloves | | |
| (5) Boots | | |
| (6) Fire axe (or other appropriate tool) | | |
| O d. Each SCBA will be provided with two spare air bottles. | | |
| ☐ 3. Crew training | Annually | ACSA |
| a. Fire team members (as identified on the Emergency Instructions | | Agreement |
| as required by 46 CFR 28.265) who will wear the fireman's | | section J 6 |
| outfits shall provide proof of Coast Guard approved basic fire | | |
| training. | | |
| 4. Fire and Safety Plan | Annually | |
| a. Up to date Fire and Safety Plans | | ACSA Guide |
| (1) General arrangement plans showing | | |
| (a) Each control station | | section J 7 |
| Control stations for controlling ships radios, main | | |
| navigation, emergency power, and where fire | | |
| reporting and fire control equipment are centralized. | | |
| (b) Location of fire resisting bulkheads. | | 46 CFR |
| (c) Location of alarms. | | 91.55-5(d) |
| (d) Location of extinguishing systems. | | |
| (e) Location of portable fire extinguishers. | | |
| (f) Means of access to different compartments and decks. | | |
| (g) Ventilation system and location of ventilation | | |
| shut-downs and dampers. | | |
| (h) Details of alarms systems. | | |
| (i) Details of extinguishing systems. | | |
| ☐ 5. Freon detectors (as required). | Annually | ACSA Guide |
| a. Installed in spaces containing main tank and compressors | | section J |
| b. Portable freon detectors should also be on board. | | |

| K - Emergency Drills | Interval | References |
|---|----------|---------------|
| ☐ 1. As part of the ACSA annual exam, drills must have been conducted | Annually | <u>46 CFR</u> |
| in the presence of an attending marine inspector. | | 28.275 |
| a. The drills must be conducted with the vessel's crew on board. | | |
| b. The drills should include: | | |
| O (1) Abandon ship | | 28.270 |
| (a) Launching survival craft | | |
| (b) Donning immersion suits or PFDs | | |
| (c) Making voice radio distress calls / using visual | | |
| distress signals. | | |
| (d) Activating general alarm | | |
| (e) Reporting inoperative alarm & fire detection systems | | |
| (f) Minimizing effects of accidental flooding | | |
| O (2) Fighting a fire | | 11 11 |
| (a) Donning Firemans outfits / SCBAs if equipped. | | |
| (b) Making voice radio distress calls | | |
| (c) Activating general alarm | | |
| (d) Reporting inoperative alarm & fire detection systems | | |
| O (3) Recover person overboard | | " " |
| (a) Activating general alarm | | |
| (b) Reporting inoperative alarm & fire detection systems | | |
| ☐ 2. Required number of qualified drill conductors in crew complement | Annually | Original ACSA |
| # crew on vessel Minimum # of qualified | | section K 1-4 |
| Drill Conductors | | |
| 15 or fewer 2 | | |
| 16-25 3 | | |
| 26-35 4 | | |
| 36 or more 5 | | |
| | | |
| ☐ 3. Record keeping of emergency drills and training | Annually | Original ACSA |
| O a. Logged by the master | | section K 6 |
| O b. Includes date of each drill | | |
| (1) Conducted not more than 30 days from previous drill. | | |
| (2) Log should indicate those that did not participate and why. | | |
| (3) Must be maintained on board for 1 year and in the main | | |
| office for 3 years. | | |
| 4. Communications among crew | Annually | Original ACSA |
| a. If crew or process workers include non-English speaking members | | section K 5 |
| (1) Vessel has tapes/CDs that provide training on emergency | | |
| procedures in the language spoken. | | |
| (a) Training tapes/CDs similar to AMSEA or | | |
| NPFVOA safety videos. | | |

| L – Emergency Communications and Navigation | Interval | References |
|---|----------|---------------|
| ☐ 1. Notification prior to discharging fixed systems into machinery spaces. | Annually | Original ACSA |
| O a. If vessel policy requires notification of the master | | section L 1 |
| (1) Must have installed communication system between | | |
| activation control station and wheelhouse. | | |
| (a) Emergency hand-held radios may be used to meet this | | |
| requirement. | | |
| Must be located on bridge, and | | |
| At fixed fire extinguisher system control stations. | | |
| ☐ 2. Procedures for activating the fixed extinguishing system | Annually | Original ACSA |
| O a. Must have clear written procedures. | | section L 2 |
| O b. Signed by Master and Chief Engineer. | | |
| ☐ 3. Automatic Identification System (AIS) | Annually | 33 CFR 164.46 |
| O a. Fish processing vessels greater than 65 feet must have an approved | | |
| AIS installed and operational. | | |
| ☐ 4. Global Maritime Distress Signal System (GMDSS) | Annually | NVIC 3-99 |
| a. Fish Processing Vessel 300 GT and over. | | Table 5 |
| O (1) Search and Rescue Transponder (SART) | | 47 CFR |
| (a) < 500 GT 1 SART | | 80.1095(b) |
| (b) $\geq 500 \text{ GT } 2 \text{ SARTs}$ | | |
| O (2) 3 VHF handheld transceivers | | 80.1095(a) |
| (a) Must operate on channel 16 and one other channel. | | |
| Channel 6 recommended | | |
| (b) NOTE: A transceiver permanently installed in an | | |
| liferaft may be counted toward this requirement. | | |
| O (3) 2 VHF radio installation | | NVIC 10-99 |
| (a) Capable of operating on: | | Table 5 |
| • Channel 6 (156.3 MHz), | | |
| • Channel 13 (156.65 MHz) | | |
| • Channel 16 (156.8 MHz) | | |
| (4) 1 MF radio installation (Single Side Band) | | <u>47 CFR</u> |
| (a) Capable of operating on: | | 80.855 |
| • 2182 kHz, | | |
| • & 2 other frequencies between (1605-3500 kHz) | | |
| O (5) 1 NAVTEX receiver. | | 80.1085(a)(4) |





| Section | Section Title | USCG District Commander | Accepted Organization (ABS / DNV) | Surveyor from a Similarly Qualified Organization | USCG Marine Inspector | USCG Fishing Vessel Examiner | Naval Architect |
|---------|--|----------------------------|---|---|-------------------------------------|---------------------------------------|--------------------|
| Α | ACSA Enrollment (Exemption Letter) | Every two years | | | | | |
| А | ACSA Exemption Renewal Examination | | | | Every Two Years | | |
| А | ACSA Mid-period Examination | | | | Annually | | |
| А | Certificate of Compliance or Coast Guard exam to include (46 CFR 28) (33 CFR 151 & 155) | | Annually | Annually | Annually | Annually | |
| В | Stability Tests & Reports | | 5 Years | | | | 5 Years |
| С | Drydock / Internal Structural Exam | | | | Twice in 5 Years, NTE 3 Years | | |
| D | Tail Shaft Exam | | | | 5 Years | | |
| E | Hull Audio Gauging | | | | 5 Years | | |
| F | Watertight & Weather- tight Closures | | | | Annually | Annually | |
| G | Machinery Inspection | | | | Annually | | |
| Н | Life Saving Arrangements | | | | Annually | Annually | |
| I | Fixed Fire Fighting Arrangements | | | | Annually | Annually | |
| J | Other Fire Fighting Equip & Plans | | | | Annually | Annually | |

NOTES

NOTES